Option A A proposed 3 metre wide footpath. This is likely to have the least visible impact to the Park. Route alignment to run to the Cricket pitch side of the hedgeline. Associated works will require:

- The resite of some existing senior play equipment

Option B Most direct line through the Park. A A 3 metre wide footpath. The route is proposed to follow the lowest level of the park following natural ground contours along the existing hedge line to minimise any visual impact on the natural setting. Associated works required to include:

- Relocation of springy in play area to front of existing access/ maintenance gate,relocate gates to end of play area.
- Extend timber fencing beyond play area at new entrance to prevent children running into the path of cyclists and new footpath leading to the play area

Option C A 3 metre wide footpath (where tree alignment permits). This is proposed to follow the existing footpath along the line of the river.

New drop kerb to enable access from the car park

New 1.2m wide footpath to connect existing footpaths along the car park kerb line

Access to Darley Barn unaffected

Existing vehicular access to remain.

Existing Footpath to cafe area unaffected

Option A

Option B

Option C

Cricket Pitch

Existing play area

Picnic area

Option A to run parallel to the existing wildlife area bund on level ground.

Option B

Option A

Option C 3 metre wide footpath following the existing footpath along the riverbank

Option A Wooded area prone to localised flooding. Footpath level to be raised and drainage improvements carried out

Option A

Option A Footpath to curve out slightly before re-joining the existing footpath to improve visibility. Footpath to cross over footbridge

Option C

Balustrades

Splay out path to improve visibility

Remove existing surfacing and lay new stone flag paving to the front of the balustrades

Repair and reinforce instances of damage to the river embankment

Darley Playing Fields

Footpath proposal to follow the existing desire line through the Park and join to the existing surfaced path adjacent to the Rowing Club.

River Derwent

Start of new proposed 3 metre wide surfaced footpath to adjoin existing surfaced path

Proposed footpath alignment options

Proposed surfaced footpath following existing alignment

Option A Footpath alignment

Option B Footpath alignment

Option C Footpath alignment

Possible surfacing and furniture options

Addagrip Terrabound Rustic sample and insitu at Kew Gardens

Bituchem colourtex sample and insitu in an historic landscape setting

Traditional wooden directional signage

© Crown copyright and database rights 2014 Ordnance Survey 100024913

AMENDMENT DETAILS	By	Chkd	Date

DRAWN BY	CHECKED BY	APPROVED BY	SCALE @A3
ROL			NTS
Date 06/04/16	Date	Date	

ORIGINAL DRAWING SIZE A1

Project Reference Number

Drawing Number

DERBY CITY COUNCIL

NEIGHBOURHOODS DIRECTORATE

Acting Strategic Director for Neighbourhoods

Christine Durrant

Council House,Corporation Street

Derby DE1 2FS

PROJECT TITLE

Darley Park path

DRAWING TITLE

Proposed route options